

Instrumentation & Monitoring Procurement – HK Feedback

James Sze

28 November 2024

Agenda


- Update of ELS Design and Control Practice in Hong Kong
- Instrumentation and monitoring procurement
- Case example of application of OM
- Ongoing and planned major infrastructure projects that have opportunities to apply OM

Hong Kong ELS Design Practice Update


Revamped guidebook on Deep Excavation Design and Construction GEO Publication No. 1/2023

- Published in December 2023
- Review design standards
- Recommend **practical** solutions
- **Rationalise** control mechanism

Aim to achieve economic designs of ELS works



ARUP



Enhanced Control Mechanism


- **Separate the control mechanism** for serviceability and safety issues
- Take **pragmatic actions** to prevent suspension of works due to ground settlement
- Pre-plan to minimise disruption to public, e.g. **quick repaving of road surface and pavement** shall be carried out when reaching the Action Levels




What do various parties need to do ?

- **Mutual trust** with the stakeholders to establish **realistic and practical** Action Levels
(e.g. client's undertaking letter)
- **Communicate** with Utility undertakers, maintenance departments and authorities to agree on response actions at appropriate levels
(e.g. prior agreement should be sought)
- **Plan ahead** and **take prompt action** to reduce serviceability issues and eliminate unnecessary suspension of works
(e.g. contract provision for quick re-paving of road and pavement, etc)

5-level (5A) Control Mechanism



Historical representative data of total ground settlement vs maximum excavation depth



Comparison with OM's Context

Green

- Inspect and/or carry out condition survey if needed
- Prepare response plan & enhance monitoring if needed

Amber

- Carry out **pre-determined actions** including utility /road serviceability check & remedial /repairing works
- Carry out detailed investigation
- **Formulate** and carry out contingency plan for reaching Lv2
- Formulate **emergency plan** for reaching Lv3

Red

- Suspend works and formulate **works resumption** plan
- Carry out emergency plan if needed, condition survey & investigation
- **Revise design** & method statement
- **Predict remaining movement** & establish trigger values for further response action

0 to < 20mm

20mm to < 0.5%H

≥ 0.5%H

Alert	Alarm	Action Lv1	Action Lv2	Action Lv3	
10 mm	15 mm	20 mm	0.3% H (25 – 60 mm*)	0.5% H (30 – 100 mm*)	Ground settlement (Cumulative)
1:600	1:500	1:400	1:350	1:300	Services tilting
1:1000	1:750	1:600	1:550	1:500	Building tilting

Typical Instrumentation & Monitoring Procurement Practice in Hong Kong

Instrumentation & Monitoring Procurement

	MTRC Projects / large-scale infrastructure projects	Private Developments
Common contract type	<ul style="list-style-type: none"> • Design & build contract • NEC4 Option C • NEC4 Option X22 	<ul style="list-style-type: none"> • Lump-sum / Remeasurement contract • Design & build contract
Responsible party for instrumentation and monitoring	<ul style="list-style-type: none"> • Contractor to install and monitor • MTRC's Consultant (or Contractor's Consultant for D&B contract) to supervise and check in routine basis 	<ul style="list-style-type: none"> • Contractor to install and monitor • Client's Consultant to supervise and check in routine basis
Responsible party to design and review trigger levels	Project Registered Structural and Geotechnical Engineers (RSE & RGE) from MTRC/MTRC's Consultant (or Contractor's Consultant for D&B contract)	Project RSE/RGE from Client/Client's Consultant (For D&B contract, the Contractor's designer shall propose the trigger level for Project RSE/RGE to review & agree)
Independent checking / monitoring	MTRC engages independent monitoring consultants and contractors to carry out monitoring / independent checking	Not mandatory. For some clients, they may engage their in-house construction team to carry out independent checking. For projects falling within MTRC area, MTRC will engage independent monitoring contractor for joint survey
Data ownership	MTRC/Client	Client

Instrumentation & Monitoring Procurement

	MTRC Projects / large-scale infrastructure projects	Private Developments
Common types of instruments	<p>Tend to be more comprehensive and sophisticated, e.g.</p> <ul style="list-style-type: none">• settlement markers,• piezometers,• vibrograph,• tilt meters,• inclinometers,• extensometers (depends),• strain gauges,• ADMS with prisms,• real time monitoring,• Web-based digital platform and database	<p>Tend to apply simple instruments, manual survey/ measurement, e.g.</p> <ul style="list-style-type: none">• settlement markers,• piezometers,• vibrograph,• tilt plates,• inclinometers (uncommon except diaphragm wall)• extensometers,• strain gauges,• ADMS with prisms,• real time monitoring,• digital platform and database

Case example

Excavation and Lateral Support Design for
the New Admiralty Station Box


New Admiralty Station

Expanding existing underground 2-line
interchanging station to accommodate
another two new lines




New Admiralty Station

ARUP




Instrumentation Plan





Initial ELS design

ARUP




Existing 2-level
“floating” underground
Harcourt Carpark




Section A


OM – Ipso tempore (Pro-active to make modifications)



- Back analysis based on inclinometer and ground settlement readings taking during excavation
- 1st Back Analysis (Exc. to -4.5mPD) → advance excavation at area beyond carpark side




Initial ELS System




Optimised ELS System for this stage


OM – Ipso tempore (Pro-active to make modifications)



- 2nd Back Analysis (Exc. to -15mPD) → ground anchor at -13mPD replaced with internal inclined strut




Initial ELS System




**Optimised ELS System
for this stage**


OM – Ipso tempore (Pro-active to make modifications)



- 3rd Back Analysis (Exc. at -19mPD) → toe anchor @-21mPD eliminated. Strut at -16.5mPD slightly adjusted to -18.0mPD



Initial ELS System



Optimised ELS System for this stage


On-going & Planned Major Infrastructure Projects in Hong Kong

Recent Major Reclamations in HK



Future reclamation projects

- Tseung Kwan O 137 & 132 – 80ha
- Kau Yi Chau Artificial Islands – 1,000ha
- Lung Kwu Tan – 150ha
- Ma Liu Shui – 90ha
- Sunny Bay – 100ha



On-going & future underground Railways

- Tung Chung Line Extension (2.5km)
- Northern Link (11km)
- Hong Kong-Shenzhen Western Rail Link (8km)
- TKO line extension (2km)
- Priority Rail Link for KYCAI (30km)
- Central Rail Line (16km)



Underground major road tunnels

- Northern Metropolis Highway (18km, expected substantial tunnel sections)
- Route 11 tunnel section (~10km)
- Tuen Mun Bypass (8km)
- Shatin Bypass (15km)



Thank You